BRUHAT BANGALORE MAHANAGARA PALIKE

Name of work: Providing new borewells and CC Roads, drains development in Nagawara Colony, Behind Pruthvi Theatre in Ward.no.06,Thanisandra

Agency:- M/s KRIDL

SCHEDULE-B

Sl No	App Qty	Description of work	Approved Rates of M/s KRIDL		
			Unit	Rate in Figures	Rate in Words
1	1.00	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging techinical personal and labour required etc., as per Specification and direction (Sl no.13.04) PRED.SR 2019-20	Each	3881.04	Rupees Three Thousand Eight Hundred Eighty One And Paise Four Only
2	50.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding cost of casing pipes, collars, cap etc.,) Sl no. 13.01 PRED SR 2019-20	m	357.41	Rupees Three Hundred Fifty Seven And Paise Forty One Only
3	50.00	50 to 100 m	m	455.26	Rupees Four Hundred Fifty Five And Paise Twenty Six Only
4	50.00	100 to 150 m	m	469.68	Rupees Four Hundred Sixty Nine And Paise Sixty Eight Only
5	50.00	150 to 200 m	m	552.08	Rupees Five Hundred Fifty Two And Paise Eight Only
6	50.00	200 to 250 m	m	653.02	Rupees Six Hundred Fifty Three And Paise Two Only
7	50.00	251 to 300 m	m	721.00	Rupees Seven Hundred Twenty One Only
8	50.00	300 to 350 m	m	849.75	Rupees Eight Hundred Forty Nine And Paise Seventy Five Only
9	50.00	350 to 400 m	m	927.00	Rupees Nine Hundred Twenty Seven Only

EXECUTIVE ENGINEER-4
KRIDL BEMP DIVISION
BENGALURU-560 010

Executive Engi
Project Divisi
Yelahanka Zon

	App Qty	Description of work	Approved Rates of M/s KRIDL		
			Unit	Rate in Figures	Rate in Words
10	60.00	Supply of ISI mark 175 mm nominal bore medium black ERW casing pipe of 5 mm thick black electric resistance continuous welded mild steel tube material confirming to IS 1387 / 1993 & manufactured from hot rolled steel skelp / stripes in random length of 4 to 7 mts both ends threaded confirming to IS 554 / 1985, one end fixed with a socket and the other and with a plastic protection end (including of all taxes) SE PRED III NO 84	Rmtr	1325.00	Rupees One Thousand Three Hundred Twenty Five Only
11	12.00	Providing and fixing to wall, ceiling and floor unplasticised PVC 6.00 kgs/sqcm working pressure with pipe fittings, wall clips etc., and making good the wall, ceiling and floor for sanitary pipelines including cost of all materials, labour charges, HOM of acquirements and testing complete as per specifications. - 250mm dias. (Page No. 88 Item No. 12.116.5) PWD SR 2018-19	Rmtr	2199.50	Rupees Two Thousand One Hundred Ninety Nine And Paise Fifty Only
12	1.00	Providing 175mm dia ms casing cap page no III it no 85 pred 12-13 sr	no	100.00	Rupees One Hundred Only
13	10.00	Providing MS Casing pipe collars page no III it no 86 pred 12-13 sr	no	150.00	Rupees One Hundred Fifty Only
14	1.00	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings . PAGE NO XLII	Unit	72126.00	Rupees Seventy Two Thousand One Hundred Twenty Six Only
15	384.00	KSRB13-3.1: Providing and fixing to wall celling and floor glavanised/ mild steel tubes (medium grade 1.27 kg /mt.) B class 50 mm dia nominal bore with all fittings (earth work in trenches to be measured and paid for separately) including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. (Page 92 ITEM NO 13.6)	Mtr	542.72	Rupees Five Hundred Forty Two And Paise Seventy Two Only
16	400.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990. P. No. 7/ I No. (2.6.4) 3cx 6.0 Sqm KPWD Electrical SR 2019-20	Mtr	205.00	Rupees Two Hundred Five Only
17	25.00	Supplying of 1.1 KV LT UG cable having aluminium condutor PVC insulated shethed, EXTREDED INNER SHEATHRD galvnised steel,stirp (2CX 10Sqm.mm wire armoured) confirming IS 3975;1990(no.of strip indicated i GTP) AND extruded PVC outer sheathing armoured cable IS 1554 part 1;1988 and confirming to GTP of group.A.4 Core 16Sqmm.P No.40/ I No.6.4.4 (4 core 16 Sqmm) KPWD Electrical SR 2019-20	Mtr	150.00	Rupees One Hundred Fifty Only
18	25.00	Labour charges for laying of 1.1 K.V class UG cable in existing trench GI Pipe / stoneware pipe /on wall/on poles as required in existing trencg/duct 6 Sqmm to 16 Sqmm)P No. 41 / I No. 6.5.1 KPWD Electrical SR 2019-20	Mtr	11.88	Rupees Eleven And Paise Eighty Eight Only
19	3.00	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class P. No. 62/ I No.7.12.1 KPWD Electrical SR 2019-20	Mtr	335.00	Rupees Three Hundred Thirty Five Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	App Qty	Description of work	Approved Rates of M/s KRIDL		
			Unit	Rate in Figures	Rate in Words
20	1.00	Supplying and fixing maniature circuit breakers on existing MCB Distribution boards using necessary fixing materials and 'C' Type curve, indicator ON/OFF, Energy cross -3 with short circuit breaking capacity of 10K And Completed wiring confirming to IEC 60898 50-63 Amps TPN (P. No. 27 I No.5.17.9) KPWD Electrical SR 2019-20	Each	2397.00	Rupees Two Thousand Three Hundred Ninety Seven Only
21	1.00	KSRB 13-7.1-4: Providing and fixing in position 65mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications NO KBS 13.2.16 / 13.13 Page No.90 Item No. 13.56 / PWD SR 2018-19	NOS	1831.68	Rupees One Thousand Eight Hundred Thirty One And Paise Sixty Eight Only
22	1.00	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete. P. No.92/ I. No. 13.81.3 PWD SR 2018-19	NOS	222.60	Rupees Two Hundred Twenty Two And Paise Sixty Only
23	1.00	Gate value 65mm nominal bore gun metal. P. No.XXVI sl No. 662 PWD SR	NOS	1694.92	Rupees One Thousand Six Hundred Ninety Four And Paise Ninety Two Only
24	1.00	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The panel board shall be fabricated on single unit in the above components for suitable pumpset. KPWD Electrical SR 2019-20	NO	8000.00	Rupees Eight Thousand Only
25	91.80	Earth work excavation By Manuall Means for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, in Soft rock/ ordinary rock not exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications. (P.No.6, I.No.2.3) PWD SR 2018-19	cum	316.94	Rupees Three Hundred Sixteen And Paise Ninety Four Only
26	25.50	KSRRB 2.6 Providing and filling sand in trenches to required depth including watring ramming with all leads and lift complete as per specifications and directed by the engineer incharge at the site (P-7 I N-2.13 SR 2018-19)	cum	2183.60	Rupees Two Thousand One Hundred Eighty Three And Paise Sixty Only
27	170.00	KSRB13-9.3 : Providing and fixing to wall, ceiling and floor high density polyethylene pipes 6.00 kgf/sq.cm working pressure 63mm outside diameter with special flange, compression type fittings, wall clips, making good the wall, ceiling and floor, including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.15.2 / 13.9 (Page no.94, Item No.13.73.2) PWD SR 2018-19	Rmtr	394.32	Rupees Three Hundred Ninety Four And Paise Thirty Two Only
28	66.30	KSRB 2-4 : Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m. and lift upto 1.5 m. including cost of all labour complete as per specifications. (Page No.7, Item No. 2.11) PWD SR 2018-19	cum	128.26	Rupees One Hundred Twenty Eight And Paise Twenty Six Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Contractor

Executive Engineer
Project Div
Yelahanka Zone

	App Qty	Description of work	Approved Rates of M/s KRIDL		
			Unit	Rate in Figures	Rate in Words
29	59.80	Removing and refixing stone slabs of drains and pointing in CM (1:3) (P.No-27,I No-5.33)	Sqm	111.30	Rupees One Hundred Eleven And Paise Thirty Only
30	575.57	KSRRB 300-1. Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications(P.No-143 &136 ,I No-19.1&17.4& 17.1) 10km lead	Cum	220.40	Rupees Two Hundred Twenty And Paise Forty Only
31	99.66	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete.(7.5cms thick)(I No-5.31.1,P No-27)	Sqm	742.00	Rupees Seven Hundred Forty Two Only
32	260.51	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)	Cum	5421.90	Rupees Five Thousand Four Hundred Twenty One And Paise Ninety Only
33	48.28	Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar & stone hammerd dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, HOM, curing complete as per specifications. KBS 5.1.13, cement mortar 1:6 (I No-34.8.2,P No-255)	Cum	4871.76	Rupees Four Thousand Eight Hundred Seventy One And Paise Seventy Six Only
34	243.20	KSRB 5-14.1 : Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. KBS No.5.4. (P.No-27,I No-5.26.2) solid concrete blocks of size 400x150x200mm	Sqm	979.44	Rupees Nine Hundred Seventy Nine And Paise Forty Four Only
35	188.85	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19)	Cum	5464.30	Rupees Five Thousand Four Hundred Sixty Four And Paise Thirty Only
36	3.64	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, paicing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19)	Tonne	73992.24	Rupees Seventy Three Thousand Nine Hundred Ninety Two And Paise Twenty Four Only
37	43.20	Providing and Fixing pre cast covering Slab 250mm thick made out of CC 1:2:4 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge	Sqm	5418.00	Rupees Five Thousand Four Hundred Eighteen Only

Executive Engineer
Project Division
Yelahanka Zone
6/11/19

Contractor

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

	App Qty	Description of work	Approved Rates of M/s KRIDL		
			Unit	Rate in Figures	Rate in Words
38	1538.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19)	Nos	432.48	Rupees Four Hundred Thirty Two And Paise Forty Eight Only
39	207.60	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6.pg no:180 Item no:24.1	Sqm	84.80	Rupees Eighty Four And Paise Eighty Only
40	547.44	Providing and Fixing pre cast covering Slab made out of CC 1:2:4 with 10cm thick and Finishing cutting ,including form work,curing,including cost of alll materials, labour,hire charges of machinery,loading,unloading,lead and lift,transportation etc ,copmplete. (Data Rate)	Sqm	2337.00	Rupees Two Thousand Three Hundred Thirty Seven Only
41	149.82	Providing granite slabs of selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., complete, 10 cms thick. Page No. 27/ Item No. 5.31.2 PWD SR 2018-19	Sqm	966.72	Rupees Nine Hundred Sixty Six And Paise Seventy Two Only
42	373.23	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials upto a lead of 1000 metrers, stacking serviceable and unserviceable materials seperately complete as per specifications. MORTH Specification No. 202.(I No-18.47,P No-140) Loading and unloading with 10km lead	Cum	978.54	Rupees Nine Hundred Seventy Eight And Paise Fifty Four Only
43	149.29	KSRRB M300-14. Excavation for roadwork in all types of soil by mechanical means including cutting and loading to tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transportation with a lead of 1.00 km and complete as per specifications MORTH Specificatio MORTH Specification No.301Loading and unloading with 10km lead (I No-19.14,P No-143)	Cum	69.06	Rupees Sixty Nine And Paise Six Only
44	1492.90	KSRRB 300-58. Compaction of original ground by mechanical means including filling in depression occuring during rolling including cost of all labour, HOM complete as per specifications.(I No-19.64,P No-147)	Sqm	6.36	Rupees Six And Paise Thirty Six Only
45	123.22	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications Clause 401 of MORTH V Revision.(I No-20.5,P No-153)	Cum	1994.92	Rupees One Thousand Nine Hundred Ninety Four And Paise Ninety Two Only

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

6/11/19

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	App Qty	Description of work	Approved Rates of M/s KRIDL		
			Unit	Rate in Figures	Rate in Words
46	223.94	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 with OPC at 360 kg/cum and coarse aggregate 0.69cum, fine aggregate 0.46cum. over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythenes in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades, textured with texturing machine, and curing including cost of all materials, labour,hire charges of machineries,all lead & lift charges etc., complete as per specifications. (P.No-176,I No-22.6.1)	Cum	5210.96	Rupees Five Thousand Two Hundred Ten And Paise Ninety Six Only
47		BESCOM DEPOSIT			
48		GST @ 12%			

H.V. 6/11/19

EXECUTIVE ENGINEER-4
KRIDL BBMP DIVISION
BENGALURU-560 010

Executive Enginee
Project Divisio
Yelahanka Zon